

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21334-00-00
Spot: NESESW Sec/Twnshp/Rge: 11-24S-17W
1015 feet from S Section Line, 2943 feet from E Section Line
Lease Name: ENLOW-MILLER Well #: 7-11
County: EDWARDS Total Vertical Depth: 4490 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4488	2010	WITH 225 SX CMT
SURF	8.625	332		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2015 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed
Plugging
Method:

PUMP BOTTOM WITH 25 SX CMT & 100# HULLS. PLUG AT 1100' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: PARTIAL
Date/Time Plugging Completed: 08/28/2015 2:00 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

PUMP DOWN 4 1/2" CASING WITH 100# HULLS & 25 SX CMT AT 2660'. SHUT IN WITH 500 PSI. 1ST PLUG AT 1100' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 35 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4389	4391		
4337	4374		
4304	4322		

KCC WICHITA
SEP 14 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed

Robert Dickerson

(TECHNICIAN)

RECEIVED
SEP - 8 2015

KCC DODGE CITY