

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-26119-00-00
Spot: SENWNESW Sec/Twnshp/Rge: 20-19S-15W
2120 feet from S Section Line, 1718 feet from W Section Line
Lease Name: NOKES Well #: 1
County: BARTON Total Vertical Depth: 3725 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3600		265 SX
SURF	8.625	946		515 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/04/2015 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: LARRY Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-3478

Proposed Plugging Method: Ordered 265 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL WitnessType: NONE
Date/Time Plugging Completed: 09/04/2015 12:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st plug @3600 w/50 sx
2nd plug @1000 w/75 sx
3rd plug @465 w/85 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

SEP 18 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

SEP 11 2015