

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-125-26218-00-00  
Spot: NENENESE Sec/Twnshp/Rge: 16-34S-14E  
2536 feet from S Section Line, 181 feet from E Section Line  
Lease Name: SCHNEIDER Well #: CF2  
County: MONTGOMERY Total Vertical Depth: 232 feet

Operator License No.: 31486  
Op Name: HORTON, JACK  
Address: 1958 COUNTY RD 3000  
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	0		0 SX
SURF	0	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/11/2015 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JACK HORTON Company: \_\_\_\_\_ Phone: (620) 249-4476

Proposed Plugging Method: 50' plug @ TD, perforate @ 225', set plug 225' to surface, lightly squeeze.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/11/2015 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Tried to get down well and hit something at 60'. Tried to wash down beside wooden plug but was unsuccessful. Set up drill rig. Pushed and drilled wooden plug down to 232'. Pulled drill pipe and perforated casing at 225'. Ran drill pipe back to 225' and circulated cement to surface. Pulled drill pipe. Hooked onto casing and squeezed 22 sacks of cement down casing to bring it around on backside. Cement came up all around the well. A total of 102 sacks of cement were used to plug this well.

Perfs:

RECEIVED  
KCC DIST #3  
SEP 01 2015  
CHANUTE, KS

DS

Remarks:

Plugged through: DP

District: 03

Signed Duane A Sims  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

SEP 03 2015

CONSERVATION DIVISION  
WICHITA, KS