

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-21609-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 6-8S-23W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: SCHWEITZER Well #: 4
County: GRAHAM Total Vertical Depth: 3870 feet

Operator License No.: 33764
Op Name: INVESTMENT EQUIPMENT LLC
Address: 17509 COUNTY RD 14
FT MORGAN, CO 80701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3862		150 SX
SURF	8.625	262		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/04/2015 10:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: JIM CHISHOLM Company: FISCHER WELL SERVICE, INC. Phone: (405) 642-9437

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Packer stuck in hole at 3716'.
Perforations: 3752' - 3757', 3773' - 3777'.
Well Bore Bridged off at 2020'

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/04/2015 1:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2020' and pumped 250 sx cement. Good circulation of cement. Pulled tubing out. Tied on to casing and squeezed with 160 sx cement. Shut in pressure 300 psi. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 200 psi.

GPS: 39.37943 -099.93752

Perfs:


Top	Bot	Thru	Comments
3752	3757		

Remarks: QUALITY CEMENT TICKET #1032

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

'SEP 08 2015