

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-02656-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 9-33S-14E
4242 feet from S Section Line, 3791 feet from E Section Line
Lease Name: PATTERSON/AGOSTO Well #: 12
County: MONTGOMERY Total Vertical Depth: 1250 feet

Operator License No.: 32255
Op Name: KANSAS ENERGY COMPANY, L.L.C.
Address: BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.5	1200		0 SX
SURF	7	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/11/2015 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: P.J. BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL
Date/Time Plugging Completed: 08/12/2015 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1165' gelled hole and spotted 2 sack plug. Pulled up to 700' and spotted 2 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 16 sacks of cement were used to plug this well.

RECEIVED
KCC DIST # 3
SEP 01 2015
CHANUTE, KS


DS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

SEP 03 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3