

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-29973-00-00Spot: NWNENENW Sec/Twnshp/Rge: 9-33S-14E5068 feet from S Section Line, 3104 feet from E Section LineLease Name: PATTERSONWell #: 1RCounty: MONTGOMERYTotal Vertical Depth: 1250 feetOperator License No.: 32255String Size Depth (ft) Pulled (ft) Comment

PROD 2.5 1200 0 SX

SURF 7 20 0 SX

Op Name: KANSAS ENERGY COMPANY, L.L.C.Address: BOX 68
SEDAN, KS 67361Well Type: GAS

UIC Docket No:

Date/Time to Plug: 08/06/2015 12:00 AMPlug Co. License No.: 32884Plug Co. Name: ELMORE'S, INC.Proposal Rcvd. from: P.J. BUCK

Company:

Phone: (620) 725-3636

Proposed Surface and production cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Pull out and
Plugging perforate at 700' and 350'. Run 1" back in and spot 50' of cement at 700'. Pull up to 350' and cement to surface.
Method:

Plugging Proposal Received By: DUANE SIMSWitnessType: PARTIALDate/Time Plugging Completed: 08/07/2015 2:00 PMKCC Agent: DUANE SIMS**Actual Plugging Report:**

Ran 1" to 1175' gelled hole and spotted 2 sack plug. Pulled up to 700' and spotted 2 sack plug.
Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 16
sacks of cement were used to plug this well.

Perfs:RECEIVED
KCC DIST # 3

SEP 01 2015

CHANUTE, KS

DS

Remarks:Plugged through: TBGDistrict: 03

Signed

Duane A. Sims

(TECHNICIAN)