

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20423-00-00  
Spot: NE Sec/Twnshp/Rge: 27-21S-41W  
3960 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: HCU Well #: 2711-B  
County: HAMILTON Total Vertical Depth: 2769 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2728	0	WITH 625 SX CMT
SURF	8.625	237		WITH 175 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/31/2015 3:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: REUBEN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/01/2015 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

RUN TBG TO 2665' & SPOT 190 SX CMT. TAG TOC IN 5 1/2" AT 1120'. RUN TBG TO 1110' & CIRCULATE CMT TO SURFACE WITH 110 SX CMT. TOOH WITH TBG & TOP OFF CASING WITH 5 SX CMT & ANNULUS WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2758	2767		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Ken Jehlik  
JA (TECHNICIAN)

RECEIVED  
SEP - 8 2015  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION  
SEP 18 2015  
CONSERVATION DIVISION  
WICHITA, KS