

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-00155-00-00  
Spot: SESENW Sec/Twnshp/Rge: 24-29S-34W  
2761 feet from S Section Line, 2748 feet from E Section Line  
Lease Name: WRIGHT J B Well #: 2-24  
County: HASKELL Total Vertical Depth: 2774 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		755		WITH 20 SX CMT
PROD	7	2598	0	WITH 300 SX CMT
SURF	10.75	678		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2015 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: FIND FREE POINT & CUT. CIRCULATE MUD & SPOT 40 SX CMT. PLUG AT 1680' WITH 40 SX CMT. RUN BOND LOG. TOC BELOW 678' PERFORATE & CIRCULATE TO SURFACE WITH 280 SX CMT. TOC ABOVE 678' RUN TBG TO 725' CIRCULATE WITH 120 SX CMT. FILL ANNULUS WITH 10-25 SX CMT & PRESSURE TO 300 PSI.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/24/2015 4:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

1ST PLUG AT 2000' WITH 40 SX CMT. 2ND PLUG AT 1690' WITH 40 SX CMT. TOC @ 655'. SET CIBP @ 755'. 3RD PLUG AT 725' WITH 20 SX CMT. PERFORATE AT 560' & CIRCULATE TO SURFACE WITH 200 SX CMT. TOP OFF HOLE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2556	2774		

**KCC WICHITA**  
SEP 14 2015  
RECEIVED  
**KCC WICHITA**  
SEP 14 2015  
RECEIVED

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature]  
SA (TECHNICIAN)

RECEIVED  
SEP - 3 2015  
KCC DODGE CITY