

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-00490-00-00  
Spot: NWNWNWSE Sec/Twnshp/Rge: 2-30S-33W  
2540 feet from S Section Line, 2540 feet from E Section Line  
Lease Name: BECKER Well #: 1  
County: HASKELL Total Vertical Depth: 2810 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 5100  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		625		
PROD 7		2632	0	WITH 500 SX CMT
SURF 10.75		495		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/25/2015 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUG AT 1900' WITH 100 SX CMT. TAG CMT. IF 1650' OR HIGHER LOAD HOLE WITH MUD & TEST AT 500 PSI. RUN CMT BOND LOG. IF TOC IS IN 10 3/4" SHOE RUN TBG TO 650' CIRCULATE INSIDE 7" WITH 115 SX CMT. FILL ANNULUS WITH 10-20 SX CMT & PRESSURE TO 300 PSI. IF TOC IS BELOW 10 3/4" SHOE, PERFORATE AT 25' ABOVE TOC & CIRCULATED WITH 350 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/26/2015 3:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

8/25/15: PUMP 100 SX CMT WITH 100# HULLS AT 1900'. 8/26/15: TOC @ 1452'. FLUID AT 300' FROM SURFACE. SET CIBP @ 625'. RUN TBG TO 600' & CIRCULATE CMT TO SURFACE WITH 120 SX CMT. PUMP 10 SX CMT DOWN BACKSIDE. HELD AT 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2606	2802		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed   
5A (TECHNICIAN)

RECEIVED  
SEP - 3 2015  
KCC DODGE CITY 