

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-00632-00-00
Spot: NWSESWNE Sec/Twnshp/Rge: 35-22S-36W
3259 feet from S Section Line, 1932 feet from E Section Line
Lease Name: SCHAEFFER Well #: 1
County: KEARNY Total Vertical Depth: 2716 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		914		
CIBP		2553		WITH 10 SX CMT
PROD 7		2603	0	WITH 100 SX CMT
SURF 10.75		272		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/27/2015 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: REUBEN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/28/2015 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2553' WITH 10 SX CMT. PLUG AT 2200' WITH 50 SX CMT. SET CIBP @ 914' OVER CASING LEAK. PERFORATE AT 875'. RUN TBG & PACKER TO 600'. INJECTION RATE 2 BPM @ 800 PSI. SPOT 75 SX CMT LEAVING 30 SX CMT OUTSIDE THE PERFS & 45 SX CMT INSIDE THE 7". PERFORATE AT 316'. CIRCULATE CMT TO SURFACE FROM 316' LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2603	2716		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Ken Jehlik

RECEIVED
SEP - 3 2015
KCC DODGE CITY

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

SEP 18 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3