

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25297-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 1-18S-15W
1500 feet from N Section Line, 2150 feet from E Section Line
Lease Name: STOSS Well #: 1
County: BARTON Total Vertical Depth: 3606 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3607		175 SX
SURF	8.625	471		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/28/2015 8:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS Phone: (214) 219-8883

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 15 sx gel and 200 # hulls.
Well has been squeezed from 636' to surface with 200 sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/28/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1040' and 1500'.
Ran tubing to 3455' and pumped 15 sx gel then pumped 50 sx cement on bottom with 100 # hulls. Pulled tubing to 1500' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 1000' and pumped 50 sx cement. Pulled tubing to 500'. Circulated cement to surface with 50 sx cement. Pulled tubing. Topped off with 10 sx cement.

GPS: 38.66766 -098.75999

Perfs:

Top	Bot	Thru	Comments
3472	3476		
3458	3462		
3450	3455		
3441	3445		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

SEP 03 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 18 2015

CONSERVATION DIVISION
WICHITA, KS