

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-13184-00-00
Spot: SENWSESE Sec/Twnshp/Rge: 6-21S-11W
923 feet from S Section Line, 910 feet from E Section Line
Lease Name: DIETS (VEEDER) Well #: 6
County: STAFFORD Total Vertical Depth: 3520 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		650		WITH 2 SX CMT
CIBP		3370		WITH 2 SX CMT
PROD	5.5	3519	0	WITH 75 SX CMT
SURF	8.625	252		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2015 11:20 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: SET CIBP @ 3370' WITH 2 SX CMT. SET CIBP @ 650' WITH 2 SX CMT. FILL WITH WATER & PRESSURE CASING TO 400#. PERFORATE AT 625'. RUN TBG INTO CASING. PUMP 50 SX CMT & 100# HULLS. WAIT FOR CMT & FIND TOC. PERFORATE AT 300' & CIRCULATE CMT TO SURFACE BOTH INSIDE & OUT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2015 12:20 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 3370' WITH 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SET CIBP @ 650' WITH 2 SX CMT. LOADED HOLE & PRESSURED TO 500#. PERFORATE AT 625' & CIRCULATE CMT TO SURFACE BOTH INSIDE & OUT WITH A TOTAL OF 355 SX CMT. 9/1/15: CMT AT 105'. TOPPED OFF WITH 1 1/2 YARDS OF READY MIX.

Perfs:

Top	Bot	Thru	Comments
3424	3470		

KCC WICHITA
SEP 14 2015
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed



SA

(TECHNICIAN)

RECEIVED
SEP - 8 2015
KCC DODGE CITY