

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-20771-00-00
Spot: NENENE Sec/Twnshp/Rge: 32-1S-35W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: CAHOJ Well #: 1
County: RAWLINS Total Vertical Depth: 4410 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4425		140 SX
SURF	8.625	313		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/20/2015 10:00 AM
Plug Co. License No.: 34737 Plug Co. Name: UNITED WELL SERVICE, LLC
Proposal Rcvd. from: K. ROBERT WATCHOUS Company: PALOMINO PETROLEUM INC. Phone: (316) 799-1000

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement and 600 # hulls.
8 5/8" surface casing set at 313' w/200 sx cement. 4 1/2" production casing set at 4425' w/140 sx cement. TD 4410'.
Perforations: 4366' - 4370', 4274' - 4278' and 4164' - 4166'. Well is non-commercial.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2015 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 3115', 2440' and 285'. Ran tubing to 4160' and pumped 100 sx cement w/350 # hulls. Pulled tubing to 2900' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1450' and pumped 220 sx cement. Manipulated valves to force cement to surface from 4 1/2" casing and 8 5/8" surface casing. 8 5/8" surface casing had severe leak below braden head. Both casings CWC. Pulled tubing to surface. Topped off casings with 5 sx cement.

Perfs:

Top	Bot	Thru	Comments
4366	4370		
4274	4278		
4164	4166		

Remarks: CONSOLIDATED OILWELL SERVICES TICKET # 34,737

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

KCC WICHITA

SEP 04 2015

RECEIVED

Form CP-2/3

AUG 25 2015