

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kiowa County, Sec. 34 Twp. 27S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NE

Lease Owner Mull Drilling Company & Walters Drilling Co.

Lease Name Brensine 'E' Well No. 2

Office Address 1625 Wichita Plaza Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 11 19 65

Application for plugging filed 10-11-65 19

Application for plugging approved 10-11-65 19

Plugging commenced 10-11-65 19


Plugging completed 10-11-65 19

Reason for abandonment of well or producing formation

commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 4938 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION.	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	555'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug @ 300' w/ 25 sacks cement
Top plug @ 40' w/ 10 sacks cement.
Rat hole - 2 sacks

RECEIVED
STATE CORPORATION COMMISSION

NOV 7 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.

Address 510 Orpheum Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Robert F. Walters (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God


(Signature) Robert F. Walters

510 Orpheum Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of October, 19 65

Juanita M. Green Notary Public.

My commission expires October 4, 1967



DRILLER'S LOG

COMPANY: MULL DRILLING CO. & WALTERS DRILLING CO.
 1625 WICHITA PLAZA
 WICHITA, KANSAS

WELL NAME: BRENSING 'E' #2
 C NW NE SEC. 34-27S-20W
 KIOWA COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
 510 ORPHEUM BUILDING
 WICHITA, KANSAS

ROTARY DRILLING COMMENCED: SEPTEMBER 29, 1965
 ROTARY DRILLING COMPLETED: OCTOBER 11, 1965

ELEVATION: 2291 KB

CASING RECORD: 8 5/8" @ 555' w/ 275 sx. cement

LOG

0 - 130	Sand
130 - 545	Shale
545 - 560	Sand
560 - 590	Shale
590 - 1277	Red Bed and Shale
1277 - 1318	Anhydrite
1318 - 1800	Shale and Shells
1800 - 2260	Shale and Lime Streaks
2260 - 2465	Shale and Lime
2465 - 2728	Lime
2728 - 3260	Lime and Shale
3260 - 3537	Shale and Lime
3537 - 3675	Lime and Shale
3675 - 3870	Shale and Lime
3870 - 4295	Lime and Shale
4295 - 4369	Lime
4369 - 4460	Lime and Shale
4460 - 4657	Lime
4657 - 4725	Lime and Shale
4725 - 4764	Lime
4764 - 4864	Lime and Shale
4864 - 4886	Core #1
4886 - 4928	Miss. Lime and Chert
4928 - 4938	Lime and Chert
<u>4938</u>	<u>Rotary Total Depth - D & A</u>

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 1 1965
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY

Robert F. Walters
 ROBERT F. WALTERS, Partner

Subscribed and sworn to before me this 28th day of October, 1965.

Juanita M. Green
 Juanita M. Green, Notary Public

My Commission Expires:
 October 4, 1967

