

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20,556-0000

LEASE NAME MC FADDEN B

WELL NUMBER #1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 34 TWP. 27 RGE. 20W (E) or (W)

COUNTY KIOWA

Date Well Completed 9/10/79

Plugging Commenced 12/4/89

Plugging Completed 1/30/90

LEASE OPERATOR J. MARK RICHARDSON

ADDRESS 155 N. MARKET SUITE 840 WICHITA, KS. 67202

PHONE# (316) 262-3192 OPERATORS LICENSE NO. 5414

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? DODGE CITY

Is ACO-1 filed? YES If not, Is well log attached? _____

Producing Formation MISS Depth to Top 4852 Bottom 4863 T.D. 4876

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	OIL	0	598	8 5/8	598	0
		0	4879	4 1/2	4879	2712

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
dump sand to 4790, dump bail 4 cr cement, cut at & pull 2712 ft. of 4 1/2 cs. pump 4 sk hulls, 10 sk gel, 50 sk cement, 10 gel, 1 hull, start cement, cement, cement circulated to surface, washout cement, to clear pipe, 1/30/90, run tubing to 750 ft, top of cement, pump 10 sk. gel, 30 sk 60/40 poz 6% gel, pull 4jt. T. @600 ft., spot 50 sk cement plug, pull 18 jt. T. (over)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor GREENSBURG WELL SERVICE License No. 5414

Address 303 E. KANSAS GREENSBURG, KS. 67054

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

J. MARK RICHARDSON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 155 N. MARKET #840 WICHITA, KS. 67202

STATE OF KANSAS SUBSCRIBED AND SWORN TO before me this 19TH day of FEB., 1990

RECEIVED

FEB 22 1990

My Commission Expires: _____
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Notary Public

KIM SANTELLAN



spot 10 sk cement plug 60/40 poz 6% gel, well did circulate