


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County, Sec. 22 Twp. 27 Rge. 19W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C of NW NW
Lease Owner Oil Properties Co., Inc.
Lease Name Barnes B#1 Well No. _____
Office Address Andover, Kansas 67002
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 11/28/78 19____
Plugging completed 11/17/78 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4825
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	541	none
				4 1/2"	4821	3553

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 4750' and ran 4 sacks cement. Shot pipe at 4008', worked pipe and gained tension to 38", pipe parted. Pulled 19 joints. Ran overshot and hooked onto pipe. Cleared hole and shot pipe at 3798', worked pipe to 26 1/2 to 38" tension. Shot pipe at 3675', 3550', worked pipe loose and pulled 99 joints. Squeezed hole with 5 sacks hulls, 20 sacks gel, released plug and displaced with 150 sacks 60/40 pozmix, 2% and 3% cc.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1978

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KESLO CASING PULLING
CHASE, KANSAS


CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 22nd day of November, 1978



Margaret Melcher
Notary Public.

My commission expires _____

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1978

Barnes #1-B
C-NW-NW Sec 22-27S-19W
Kiowa County Kansas

Commenced: 1-7-78

CONSERVATION DIVISION
Wichita, Kansas

Completed: 1-19-78

OPERATOR: OIL PROPERTIES CO., INC.

From	Depth to	Formation	Remarks
0	565	Sand-Shale	Ran 13 jts of 28# 8 5/8" csg
565	1035	Sand-Shells	set @ 541' Cemented w/
1035	1210	Shale-Redbed	275 sks Common 2% Gel
1210	1234	Anhy	3% CC PD @ 1:00 a.m.
1234	2050	Shale-Shells	1-9-78
2050	2365	Shale-Lime	
2365	2705	Lime-Shale	
2705	2895	Shale-Lime	
2895	3840	Lime-Shale	
3840	4040	Shale-Lime	
4040	4825	Lime	Ran 13 jts of 10 1/2# 4 1/2" csg set @ 4821'
	4825		Preflused w/20 barrels of Salt Flush - Cemented w/135 sks 50/50 Posmix 18% Salt - 2% Gel PD @ 2:50 p.m. 1-19-78

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
JAMES S. SUTTON II

Subscribed and sworn to before me this 24th day of January, 1978.

Elizabeth J. Edwards
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

