

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Kiowa County, Sec. 10 Twp. 27S Rge. (E) 20 (W)

Location as "NE/CNW%SW%" or footage from lines: C SE SW  
Lease Owner: Pickrell Drilling Company  
Lease Name: Einsel Well No. 1  
Office Address: 705 Fourth National Bank Bldg., Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole  
Date well completed: January 7, 19 62  
Application for plugging filed: January 7, 19 62  
Application for plugging approved: January 7, 19 62  
Plugging commenced: January 7, 19 62  
Plugging completed: January 7, 19 62  
Reason for abandonment of well or producing formation: Dry Hole

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Fred W. Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4985 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	367'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud to 350'. Set Plug. Cemented with 20 sacks cement. Heavy mud to 35'. Set Plug. Cemented with 10 sacks cement to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
1-19-62 JAN 17 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor: Pickrell Drilling Company  
Address: 705 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Gerald W. Pike (~~WIDOWER~~) (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald W. Pike  
Gerald W. Pike  
705 Fourth National Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of January, 19 62

My commission expires September 24, 1962  
Maxine Johnson  
Notary Public.



**ROTARY DRILLING LOG**

COMPANY: Pickrell Drilling Company  
 705 Fourth National Bank Bldg.  
 Wichita 2, Kansas

LOCATION: Einsel #1, - C SE SW, Sec. 10-27S-20W,  
 Kiowa County, Kansas

Rotary Drilling Commenced 12/18/61  
 Rotary Drilling Completed 1/7/62

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
 Wichita, Kansas

CASING RECORD: 367' (9 jts.) 8 5/8" 19# Surface Casing cemented w/260 sacks cement.  
 Circulated. No oil string run. D & A

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

	<u>Circulated for Samples</u>	
110'	Sand	4255'
265'	Red Shale	4295'
310'	Sand	4840'
370'	Blue Shale	4855'
515'	Shale	4865'
635'	Sand	4875'
738'	Red Beds	4885'
755'	Blaine	4895'
1305'	Red Bed	4905'
1345'	Anhydrite	4920'
2170'	Shale & Shells	4985'
2235'	Lime & Shale	
2405'	Lime & Shells	
2560'	Lime & Shale	<u>Slope Test</u>
3205'	Lime	1500' 0°
3700'	Lime & Shale	2500' 0°
3795'	Lime	3500' 0°
3885'	Lime, Shale & Sand	4107' 0°
4088'	Lime	
4305'	Lime & Shale	<u>S. L. M.</u>
4470'	Lime	2000'
4525'	Lime & Shale	3000'
4600'	Lime	4000'
4640'	Lime & Shale	
4690'	Lime	
4735'	Lime & Shale	
4802'	Lime	
4865'	Lime & Shale	
4985'	Mississippi R.T.D.	

RECEIVED  
 STATE CORP. COMMISSION  
 JAN 10 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, Gerald W. Pike, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By Gerald W. Pike  
 Gerald W. Pike Attorney-in-Fact

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } ss.:

On this 17th day of January, 1962, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared Gerald W. Pike, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company; for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: September 24, 1962

Maxine Johnson  
 Maxine Johnson Notary Public