

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15 097- 21,261-0000

LEASE NAME Einsel Trust

WELL NUMBER 3

2970 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 10 TWP. 27 RGE. 20 ~~XX~~X or (W)

COUNTY Kiowa

Date Well Completed 5-8-88

Plugging Commenced 5-9-88

Plugging Completed 5-9-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Crosswind Petroleum, Inc., Mid-Continent Energy Corp.
ADDRESS 155 N. Market, Suite 200, Wichita, KS 67202

PHONE# 316) 262-4132 OPERATORS LICENSE NO. 4254 & 5205

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-2-88 (date)

by Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Will be filed by operator If not, Is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4950

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

1st plug at 1345' w/50 sx

2nd plug @ 730' w/ 50 sx

3rd plug @ 40' w/10 sx

15 sx in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Company, Inc. License No. 5929

Address 620 Hubbard, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.


John Armbruster (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Armbruster

(Address) 620 Hubbard, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this May day of 1988

Deborah Hoque
RECEIVED
STATE CORPORATION COMMISSION



Expires: _____

MAY 17 1988
5-17-88
CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 07-87

DRILLERS WELL LOG

DATE COMMENCED: 5-1-88

DATE COMPLETED: 5-8-88

Crosswind Petroleum, Inc. &
Mid-Continent Energy Corp.
Einsel Trust #3
S/2 SW NW
Sec. 10-27-20W
Kiowa County, Kansas

0 - 95' Top Soil, Sand
95 - 1308' Shale, Red Bed, Shale
1308 - 1349' Anhydrite
1349 - 4088' Lime & Shale
4088 - 4093' Shale
4093 - 4229' Shale, Lime & Shale
4229 - 4608' Lime
4608 - 4775' Lime, Chert
4775 - 4846' Shale, Lime
4846 - 4950' Chert, Lime
4950' RTD

Surface Pipe:
Set new 8 5/8", 24#
at 717' w/350 sacks
60/40 Pozmix, 2% gel,
3% C.C.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

JOHN ARMBRUSTER of lawful age, does swear and state that the facts
and statements herein are true and correct to the best of his knowledge.


John Armbruster

SUBSCRIBED AND SWORN to before me this 12 day of May, 1988.


Notary Public RECEIVED
STATE CORPORATION COMMISSION



MAY 17 1988

CONSERVATION DIVISION
Wichita, Kansas