

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 9 Twp. 27S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE SE

Lease Owner Mull Drilling Co. & Walters Drilling Co.

Lease Name Einsel 'F' Well No. 1

Office Address 1625 Wichita Plaza Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-3-66 19

Application for plugging filed 11-3-66 19

Application for plugging approved 11-3-66 19

Plugging commenced 11-3-66 19


Plugging completed 11-3-66 19

Reason for abandonment of well or producing formation

commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation Depth to top Bottom Total Depth of Well 4998 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	600'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug @ 450' w/ 25 sacks cement.
Hole filled up to 40' - Set another plug @ 40' w/ 10 sacks cement.
2 sacks for rathole

RECEIVED
NOV 21 1966
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.

Address 400 Insurance Building - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Robert F. Walters

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) X [Signature]

400 Insurance Building, Wichita, Kansas 67202 (Address)

Subscribed and sworn to before me this 9th day of November, 1966

My commission expires October 4, 1967

[Signature] Notary Public.



DRILLER'S LOG

COMPANY: MULL DRILLING CO. & WALTERS DRILLING CO.
 1625 WICHITA PLAZA BUILDING
 WICHITA, KANSAS

WELL NAME: EINSEL 'F' #1
 C SE SE SEC. 9-27S-20W
 KIOWA COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
 400 INSURANCE BUILDING
 WICHITA, KANSAS

ROTARY DRILLING COMMENCED: OCTOBER 21, 1966
 ROTARY DRILLING COMPLETED: NOVEMBER 3, 1966

ELEVATION: 2289 KB

CASING RECORD: 8 5/8" @ 600' w/ 275 sacks cement.

LOG

0 - 90	Sand
90 - 210	Shale
210 - 245	Sand
245 - 580	Shale and Shells
580 - 600	Sand
600 - 735	Shale and Red Bed
735 - 750	Blaine
750 - 1265	Shale and Shells
1265 - 1292	Shale
1292 - 1317	Anhydrite
1317 - 1610	Shale and Shells
1610 - 2510	Shale and Lime
2510 - 2635	Lime and Shale
2635 - 2950	Lime
2950 - 3096	Lime and Shale
3096 - 3190	Shale and Lime
3190 - 3505	Lime and Shale
3505 - 3775	Shale and Lime
3775 - 4135	Lime and Shale
4135 - 4655	Lime
4655 - 4725	Lime and Shale
4725 - 4760	Lime
4760 - 4830	Lime and Shale
4830 - 4883	Lime
4883 - 4922	Lime and Chert
4922 - 4998	Lime
<u>4998</u>	<u>Rotary Total Depth - D & A</u>

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 21 1966
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY Robert F. Walters
 ROBERT F. WALTERS, Partner



Subscribed and sworn to before me
 this 9th day of November, 1966.

Juanita M. Green
 Juanita M. Green, Notary Public
 My Commission Expires: October 4, 1967