

STATE CORPORATION COMMISSION
200 Colorado Darby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20623-0000

LEASE NAME Einsel H

WELL NUMBER 1

330 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 4 TWP. 27S RGE. 20 (E) or (W)

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced 12-01-95

Plugging Completed 12-05-95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oil Producers, Inc. of Kansas

ADDRESS P.O. Box 8647, Wichita, Kansas 67208

PHONE # (616) 672-6373 OPERATORS LICENSE NO. _____

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-01-95

(date)

by Steve Middleton

(KCC District Agent's Name)

Is ACO-1 filled? Yes _____ If not, is well log attached? _____

Producing Formation UNK Depth to top 4844' Bottom 4846 r.c. 4940

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface			8 5/8"	615	0
	Production			4 1/2"	4938	2493

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Bottom plug; sanded off to 4790' 4 sks of cement. Halliburton mixed and pumped 300 lbs. of hulls with H2O. Pumped 10 sks of gel. Pumped 50 sks cement @ 12.8 ppg 40-60 poz 6% gel. Mixed 10 sks of gel. Pumped 100 lbs. hulls with water. Released plug, mixed pumped 150 sks of cement @ 12.8 ppg. Finish mixing cement. Maximum psi 490 psi shut in pressure 300 lbs.

Name of Plugging Contractor D.S. & W. Well Servicing, Inc.

License No. 6901

Address P.O. Box 231, Claflin, Kansas 67525

RECEIVED
STATE CORPORATION COMMISSION
DEC 7 1995 12-7-95

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas

STATE OF Kansas COUNTY OF Barton

Arthur P. Strube

(Employee of Operator or Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.

(Signature) Arthur P. Strube

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 95

Karlynn K. Beck
Notary Public

My Commission Expires: 9-28-98

USE ONLY ONE SIDE OF EACH FORM

KARLYNN K. BECK
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 9-28-98

Form CP-1
Revised 05-88