


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kiowa County, Sec. 4 Twp. 27 Rge. 20 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NW  
Lease Owner Anador Resources, Inc.  
Lease Name EINSEL Well No. 1-4  
Office Address Quebec Court 1, Suite 320, 5700 S. Quebec, Englewood, CO 80111  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above Section Plat

Date Well completed 6/20 1981  
Application for plugging filed 6/20 1981  
Application for plugging approved 6/20 1981  
Plugging commenced 6/20 1981  
Plugging completed 6/20 1981  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4950'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	118'	13-3/8"	118'	none
		0	620'	8-5/8"	620'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

40 sks @ 920', 50 sks @ 600',  
10 sks @ 40', 10 sks rathole;  
50/50 poz., 4% gel, 3% c.c.,  
Plug down 8:30 P.M., 6/20/81  
By Sun Cementing

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.  
James R. Holley (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James R. Holley  
P.O. Box 1389, Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 19 81



Ruth Brack  
Notary Public.

My commission expires \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

JUL - 2 1981

CONSERVATION DIVISION  
Wichita, Kansas

DRILLER'S WELL LOG

DATE COMMENCED: 06/09/81  
 DATE COMPLETED: 06/20/81

Anador Resources, Inc.  
 EINSEL No. 1-4  
 SW SW NW  
 Sec. 4, Twp. 27S, Rge. 20W,  
 Kiowa County, Kansas

ELEVATION: 2281' G.L.  
 2286' K.B.

2523 - 3324' Lime, shale  
 3324 - 3458' Lime  
 3458 - 4104' Lime  
 4104 - 4240' Shale  
 4240 - 4248' Lime, shale  
 4248 - 4662' Lime  
 4662 - 4782' Lime, shale  
 4782 - 4886' Chert, lime  
 4886 - 4950' Chert, lime  
 4950' RTD

FORMATION DATA:  
 Chase 2523'  
 Wabaunsee 3324'  
 Tarkio 3458'  
 Heebner 4104'  
 Brown Lime 4240'  
 Lansing 4248'  
 Base KC 4662'  
 Cherokee 4782'  
 Mississippi 4886'  
 RTD 4950'

SURFACE DATA: Ran 6 jts.,  
 118' of 13-3/8" conductor pipe -  
 set @ 118' w/ 175 sks 60/40 poz.  
 3% cc., 2% gel. Cemt. circ.  
 Ran 16 jts. 24# 8-5/8" surface  
 casing; tally 613'; Set @ 620'  
 w/ 250 sks 60/40 poz., 4% gel,  
 3% c.c., & 150 sks com., 2% gel,  
 3% c.c., Cemt. circ., plug down  
 3 AM, 6/10/81, By Sun Cementing.

PLUGGING DATA: 40 sks. @ 920'  
 50 sks @ 600', 10 sks @ 40',  
 10 sks rathole; 50/50 poz.,  
 4% gel, 3% c.c., plug down  
 8:30 PM, 6/20/81, by Sun Cemtg.

A F F I D A V I T

RECEIVED  
 STATE CORPORATION COMMISSION

STATE OF KANSAS )  
 COUNTY OF BARTON ) ss.

JUL - 2 1981

CONSERVATION DIVISION  
 Wichita, Kansas

James R. Holley, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

*James R. Holley*

Subscribed and Sworn to before me this 30th day of June, 1981.



*Ruth Brack*  
 Notary Public