

15-155-19118-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Reno County. Sec. 21 Twp. 26 Rge. 9W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SE

Lease Owner Phillips Petroleum Company

Lease Name Dutton Well No. 1

Office Address Box 287, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 9 19 48

Application for plugging filed February 24 19 69

Application for plugging approved March 3 19 69


Plugging commenced March 13 19 69

Plugging completed March 15 19 69

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production July 1 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman PBD 3884'

Producing formation Viola-Miss. Chat-LKC Depth to top 3373' Bottom 3895' Total Depth of Well 4405 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
LKC	Non-Commercial	3405	3573	8-5/8"	433'	-
Mississippi Chat	Gas-Oil-Water	3906	3960	5-1/2"	4222	2197'
Viola	Oil-Water	4172	4212			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dmpd sand 3884-3400', 5 sx cmt 3400-3365'. Shot 5 1/2" csg @ 2200' - pulled 69 jts (2197.47'). Filled w/mud 3365-260'. Set 10' rock bridge 260-250'. Dmpd 25 sx cmt 250-175', mud 175-40'. Set rock bridge 40-30'. Dmpd 10 sx cmt 30' to base of cellar.

Note: Prior to re-completion attempt in LKC 1-20-69 set pkr 3917', dmpd 6 sx cmt & 1 sk calseal 3917-3884'.

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Company

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

A. T. Slagle (employee of owner) or former operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A.T. Slagle Dist. Supt.

Box 287, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of March, 1969

My commission expires 10-27-69 Notary Public.

Formation Record

Lease Dutton

Well No. 1

FROM	TO	Formation	REMARKS
0	120	Surface Sand and Clay	15-155-19118-0000
120	190	Red Bed and Shells	
190	410	Shale and Lime Shells	
410	440	Shale and Shells	
440	450	Anhydrite	
450	470	Anhydrite	
470	955	Red Bed, Shale and Shells	
855	1100	Shale and Shells	
1100	1230	Salt and Shells	
1230	1375	Shale and Lime	
1375	1450	Shale and Broken Lime	
1450	1565	Lime	
1565	1655	Lime and Shale	
1655	1710	Lime	
1710	2475	Shale and Lime	
2475	2575	Shale and Lime Shells	
2575	2740	Shale and Lime	
2740	2810	Lime	
2810	2902	Lime and Shale	
2902	3030	Lime	
3030	3103	Lime and Shale	
3103	3185	Lime	
3185	3380	Lime and Shale	
3380	3648	Lime	Top Heobner 3291'. Top Douglas Sand 3287'. Top Brown Lime 3366'. Top L.K.C. 3378'.
3648	3663	Hard Lime	
3663	3759	Lime	
3759	3900	Lime and Shale	
3900	3970	Lime	
3970	3980	Lime, Cherty	Top Cherty Mississippi 3903'. Top Kinderhook 3976'.
3980	4032	Lime and Shale	
4032	4169	Shale	
4169	4257	Lime	
4257	4269	Lime and Sand	Top Cherty Viola 4173'. Top Coarse Kin Viola 4252'. Top Simpson Sand 4261'.
4269	4310	Sand	
4310	4340	Shale and Lime Shells	
4340	4365	Lime and Sand	
4365	4375	Lime, Hard.	Top Arbuckle 4355'.
4375	4405	Lime	
	4405	T.D.	
	4150	P.B.T.D.	

Sample Log Interpretations on next page.