

WELL PLUGGING RECORD
K.A.R.-82-3-117

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

RECEIVED
JUL 24 2003
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

API NUMBER 155-21463-0000
LEASE NAME Woodson
WELL NUMBER 2-21
1650 ft. from S Section Line
1980 ft. from E Section Line
SEC. 21 TWP. 26 RGE. 9 (E) or (W)
COUNTY Reno
Date Well Completed 1-31-03
Plugging Commenced 7/8/03
Plugging Completed 7/9/03

LEASE OPERATOR R & B Oil & Gas, Inc.
ADDRESS PO Box 195, Attica, KS 67009
PHONE # (620) 254-7251 OPERATORS LICENSE NO. 31191
Character of well Gas

(Oil, Gas) D&A, SWD, input, Water Supply Well)
The plugging proposal was approved on 7/8/03 (date)
by Doug Louis (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation Severy Sand Depth to Top 2453 Bottom T.D. 3780
Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS						
CASING RECORD						
Formation	Content	From	To	Size	Put in	Pulled out
<u>Severy Sand</u>	<u>Gas</u>			<u>8 5/8</u>	<u>305</u>	<u>none</u>
				<u>4 1/2</u>	<u>2561</u>	<u>1345</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set

Sand at 1489, bail 4 sacks cement. Ripped pipe at 1345, work free. Pull 1 jt. Pump 35 sacks cement. Pull to 800, pump 35 sacks cement. Pull to 350, pump 125 sacks cement. Circulate to surface and pull rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R & B Oil & Gas, Inc.

STATE OF Kansas COUNTY OF Harper, ss.
Randy Newberry

(Employee of Operator) or (Operator) of above - described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above - described well as filled that the same are true and correct, so help me God.

(Signature) Randy Newberry
(Address) PO Box 195, Attica, KS 67009

SUBSCRIBED AND SWORN TO before me 19th day of July, 2003

Jane Swingle
Jane Swingle, Notary Public
My commission Expires: 1-6-07

