


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Reno County, Sec. 22 Twp. 26 Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines C NE NE
Lease Owner George R. Shaw
Lease Name Edna Brown Unit Well No. 2
Office Address 826 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 19
Application for plugging filed October 27 19 70
Application for plugging approved 19
Plugging commenced November 11 19 70
Plugging completed November 12 19 70
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3270 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	293'	8 5/8"	293'	none
		0	2410'	5 1/2"	2410'	1549.90

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 2400'. Set plug at 2440' with 10 sacks of cement.

Set 10' rock bridge at 290' and plugged well with 35 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1970
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 19 70

My commission expires Feb. 10, 1971

George A. Meyer
Notary Public.

STENCILED

NOV 9 1963

ORIGINAL

NO. 2 DONA BROWN UNIT

15-155-39320-0000

Well Records

Location: Ctr. NE/4 NE/4
Section 22-26S-9W
Reno County, Kansas

Commenced: July 8, 1953

Completed: July 22, 1953
(rotary)

Operator: Edwin G. Bradley
825 Union Center
Wichita, Kansas

Elevation: 1672' K/B

Production: ~~2420~~ 2420 MCF6

Contractor: Messman-Rinehart Oil Company
1432 Wichita Plaza
Wichita 2, Kansas

Casing Records: 8-5/8" @ 293' w/225 sh. cement
5-1/2" @ 2410' w/110 sh. cement

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1970
CONSERVATION DIVISION
Wichita, Kansas

*** LOG ***

Surface Clay	45
Sand	120
Shale & Shells	140
Shale & Shells, Red Bed	293
Shale & Shells	895
Shale	1210
Anhydrite	1245
Shale & Shells	1255
Shale & Lime Shells	1375
Lime & Shale	1500
Lime	1800
Lime & Shale	2145
Sand & Shale	2193
Core #1 (Sand & Shale)	2236
Sand & Shale	2275
Shale	2321
Core #2	2353
Shale & Lime	2470
Lime & Shale	2565
Shale & Lime	2708
Topoka	2757
Lime	2825
Chalky Lime	3055
Lime	3120
Lime & Shale	3190
Lime	3218
Core #3	3237
Shale & Sand	3270 R.T.D.

Sample Tops

2320' - Langdon Sand (-648)
1490' - Winfield (#182)
1769' - Council Grove (-97)
2051' - Foreker (-379)
2197' - Indian Cave Zone (-525)
2389' - Torkio Sand (-717)
2623' - Howard (-551)
2738' - Topoka (-1066)

3143 Hub.
3208 Top.
3223 Doug. Ind.

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland
J. A. Gilliland

Subscribed and sworn to before me
this 6th day of August, 1963

Barbara J. Scott
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1964