

 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
3-21-66
MAR 21 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Brensing "D" Well No. # 1

Location C NW NE Sec. 29 Twp. 27 Rge. 20 (E) (W) W

County Kiowa Total Depth 4980'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Walters Drilling Company

Address: 510 Orpheum Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 11:15AM Day 19th Month March Year 1966

The Above well was plugged as follows:

558' of 8 5/8" surface pipe, cement circulated with 290 sacks. Hole was
filled with drilling mud to 300', 1st cementing plug, bridged solid with
dry cement and 1/2 sack of hulls on fluid at 300', and cemented with 25 sacks.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and 1/2 sack of hulls on fluid at 40', and cemented
with 10 sacks to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 3/21/66

INV. NO. 2910-W