

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 31 1964
12-31-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Mull Drilling Co., Inc. (Walters Drilling Co.)

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Einsel "E" Well No. # 1

Location C. SE NW Sec. 17 Twp. 27 Rge. 20 (E) (W) W

County Kiowa Total Depth 5100

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Walters Drilling Company

Address: 510 Orpheum Bldg., Wichita, Kansas License No.

Operation Completed: Hour 6:00PM Day 30th Month Dec. Year 1964

The Above well was plugged as follows:

320' of 8 5/8" surface pipe, cement circulated with 180 sacks. Fluid level was up in the hole. 1st cementing plug and 1/4 sack of hulls was pushed in fluid to 300', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with dry cement and hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar.

Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/31/64

INV. NO. 448-W