

J.P.
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Bowers Well No. # 1

Location NE NW Sec. 23 Twp. 27 Rge. 20 (E) (W) W

County Kiowa Total Depth 4858'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 7:00PM Day 31st Month August Year 1966

The Above well was plugged as follows:

344' of 8 5/8" surface pipe, cemented with 250 sacks. 4847' of 5 1/2" long
string, cemented with 75 sacks. This is an open hole. Bottom of the hole
was sanded to 4825', and cemented with 5 sacks, through the dump bailer.
3619' of 5 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 300', rock bridge from 300' to 285', 5 sacks of cement
was mixed in a barrel, and put on plug at 285', through the dump bailer,
and let set over-night. Next day hole was bailed dry, and 20 sacks of cem-
ent was added to the plug. Hole was filled with mud to 40', rock bridge from
40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9/2/66
INV. NO. 3854-W

Signed: Archie Elving
Well Plugging Supervisor