

4 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 7 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Walters Drilling Company

Complete Address: 400 Insurance Bldg., Wichita, Kansas

Lease Name Cate Well No. # 1

Location C SE NE Sec. 33 Twp. 27 Rge. 20 (E) (W)

County Kiowa Total Depth 4932'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:30AM Day 4th Month Nov. Year 1966

The Above well was plugged as follows:

550' of 8 5/8" surface pipe, cemented with 290 sacks. 4923' of 4 1/2" long string, cemented with 125 sacks. Top perferation 4988'. Bottom of the hole was sanded to 4950', and cemented with 3 sacks, through the dump bailer. 4000' of 4 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 400', bridge plug and rock bridge from 400' to 390'. 6 sacks of of cement was mixed in a barrel, and put on plug at 390', through the dump bailer, and let set over-night. Next day hole was bailed dry, and 19 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/8/66
INV. NO. 4238-11