

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC -1 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas

Lease Name Brensing "A" Well No. # 1

Location C SE NW Sec. 33 Twp. 27 Rge. 20 (E) (W)W

County Kiowa Total Depth 5000'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company

Address: Route 2, Great Bend, Kansas License No.

Operation Completed: Hour 4:15 PM Day 26th Month Nov. Year 1965

The Above well was plugged as follows:

635' of 8 5/8" surface pipe, cement circulated with 500 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged solid
with dry cement and hulls on fluid at 300', and cemented with 50 sacks,
through the drill pipe. Hole was filled with drilling mud to 50', 2nd
cementing plug, bridged solid with dry cement and hulls on fluid at 50'
and cemented with 20 sacks to the base of the cellar. Rat and mouse
holes bridged and cemented with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 12-1-65

INV. NO. 2313-W