

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-091 - 20, 750-0000

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name J. Mark Richardson

Complete Address 640 Century Plaza Bldg. Wichita Kansas 67202

Lease Name Mc.adden B Well No. 2

Location SE-SE-SW Sec. 34 Twp 27S Rge 20W (East)(West)

County Kiowa Total Depth 4902'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated This well was completed but never produced

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase Kansas 67524 License No. 681

Operation Completed: Hour: _____ Day: 19 Month: January Year: 1983

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The surface casing was cement circulated with 450 lbs of cement. There was 4901' of 4 1/2" production pipe cemented with 150 lbs. of cement. They perforated production pipe at 4880' to 4886'. 1st plug sand off bottom, back to 4850' + put 4 lbs. of cement on top of sand. 2nd plug 5 lbs. hulls, 22 lbs. of 3-0 lb. cement 8 lbs. of released rubber plug and pumped 100 lbs. cement on top of rubber plug. They recovered 3030' of 4 1/2" pipe. The cement used was 50/50 Pans 4% gel + 3% CC. The plugging was accomplished by Halliburton Co. out of Platt MO

Amount of Surface Casing: 604' of 8 5/8" well shut in at 400 lbs

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul Luthis
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 1-26-82
INV. NO. 9122-W

Signed: _____
Conservation Division Agent
STATE CORPORATION COMMISSION

1-26-82 **RECEIVED**
JAN 26 1982
CONSERVATION DIVISION
Wichita, Kansas