

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 26 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Gabbert-Jones Inc.

Complete Address 830 Sutton Place Wichita, Ks 67202

Lease Name Einsel Well No. 1

Location C/NW/SW Sec. 10 Twp. 27 Rge. 20 (E) (W) W

County Kiowa Total Depth 4860

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Ks License No. 49

Operation Completed: Hour 2:00 PM Day 24 Month 3 Year 1970

The above well was plugged as follows:

587 ft of 8 5/8 surface pipe circulated with cement. 4859 ft of 4 1/2
long string cemented with 150 sacks. Top perf. 4852 ft. Sand
back to 4800 ft, 5 sacks cement with bailer. Pulled 2830 ft of 4 1/2.
Pumped 20 sacks gel to 450 ft. Pumped 100 sacks cement to top of
surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *L. Russell Biberstein*
Well Plugging Supervisor

INVOICED

DATE 3-27-70

INV. NO. 1639-W