

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

FORM CP-3  
1-8-82  
RECEIVED  
STATE CORPORATION COMMISSION  
AUG 04 1982

CONSERVATION DIVISION  
Wichita, Kansas

API Number 15-(160)

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Span Petroleum Co. Inc.

Complete Address 300 Sutton Plaza, Wichita, Kansas 67202

Lease Name Tralick Well No. A-1

Location C-SW-SW Sec. 14 Twp. 27 Rge. 20 (East)(West)

County Keoia Total Depth 5411'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing plugging

Address \_\_\_\_\_ License No. 687

Operation Completed: Hour: 1:00 P.M. Day: 26 Month: July Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

They set 4950' of 5 1/2" production pipe & cemented it with 170 sbs of cement. They plugged back to 4850' then perforated from 4844' to 49'. 1st plug sandbed bottom, back to 4800' dumped 5 sbs of cement on top of sand with below. 2nd plug pumping through head on 8 3/8" surface casing. Pumped 5 sbs full & 25 sbs of gell & released rubber plug & followed it with 150 sbs of cement. They recovered 2319' of 5 1/2" production pipe. The cement used was common with 3% CC.

Amount of Surface Casing: 558' of 8 3/8" cement circulated with 400 sbs of cement

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luttie  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

I was on another well at this time.

Signed: Paul A. Luttie  
Conservation Division Agent

INVOICED  
DATE 8-9-82  
842-W