

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-Docket # 66936-C

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Geac Petroleum Co. Inc.

Complete Address 300 Sutton Place, Wichita, Kansas 67202

Lease Name Fralich Well No. 2

Location C-NE-SW Sec. 14 Twp. 27 Rge. 20 (East)(West)

County Osawa Total Depth 4878'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. Inc.

Address Box 31, 332 W. Wichita, Russell, Kansas 67665 License No. _____

Operation Completed: Hour: 12:30 P.M. Day: 17 Month: May Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

*This well was drilled in & completed Jan 31 - 1961. They had bottom plugged off before plugged hole back to 612'. Then set 610' of 2 7/8" tubing, perforated & cemented tubing to top of hole. 1st plug this day Allied pumped 150 bbl of cement down the 2 7/8" tubing filling hole to 0'. The cement used was common cement with 3% cc. The shut in pressure was 500 lbs. The plugging was accomplished by Allied Cementing. This well had 5 1/2" casing in previous to the 612' plug back, it had been pulled before plug back.
Amount of Surface Casing: 557' of 8 5/8" cement circulated*

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthi
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE 5-19-82

INV. NO. 188-W

Signed: _____
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
MAY 18 1982
CONSERVATION DIVISION
Wichita, Kansas