


Form CP-3
Rev. 6-26-62


 KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 4 1966
 11-4-66
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assitant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Operator's Full Name Mull Drilling Company, Inc.
 Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas
 Lease Name Einsel Well No. # F-1
 Location C SE SE Sec. 9 Twp. 27 Rge. 20 (E) (W) W
 County Kiowa Total Depth 4998'
 Abandoned Oil Well Gas Well Input Well SWD Well D & A X
 Other well as hereafter indicated: _____
 Plugging Contractor: Walters Drilling Company
 Address: 510 Orpheum Bldg., Wichita, Kansas License No. _____
 Operation Completed: Hour 6:00AM Day 3rd Month Nov. Year 1966

The Above well was plugged as follows:

600' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid
level in the hole was at 100'. 1st cementing plug and 1/2 sack of hulls
was pushed in fluid to 450', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with
10 sacks to the base of the cellar. Rat hole bridged and cemented with
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 11/4/66INV. NO. 4231-W

Signed: Archie Elving
 Well Plugging Supervisor