

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. J. Blevins of Jones-Gebert Oil Inc. has this date requested permission to plug the following described well:

Mr. Blevin guarantees payment of the plugging fee.

Operator's full Name: Jones-Gebert Oil Inc.

Complete Address: 205 Central Bldg., Wichita, Kansas

Lease Name: Stevens Well No. # 1

Location: C SW SW Sec. 12 Twp. 27 Rge. 20 (E) (W) W

County Kiowa Total Depth 4900 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Blevin was instructed to plug the well as follows:

355' of 8 5/8" surface pipe, cemented with 275 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent