

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202
RECEIVED
STATE CORPORATION COMMISSION

APR 5 1971

CONSERVATION DIVISION
Wichita, KansasVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Myers of Barbara Oil Co. has this
date requested permission to plug the following described well:

Mr. Myers guarantees payment of the plugging fee.

Operator's full Name: Barbara Oil Co.

Complete Address: 509 Union Center Wichita, Ks

Lease Name: Einsel A Well No. 1

Location: NW/SW/NE Sec. 6 Twp. 27s Rge. 20 (E)(W) W

County: Kiowa Total Depth 4900 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Myers was instructed to plug the well as follows:

562 ft of 8 5/8 surface pipe cemented with 425 sacks, cir.

Pump 1st plug to 500 ft with 40 sacks cement. 2nd plug

to 300 ft with 25 sacks of cement. Mud to 40 ft, 1/2 sack

hulls, plug, 10 sacks cement to surface. 2 sacks cement

in rat hole. Halliburton Cementing Co. Great Bend, Ks

Very truly yours,

Russell B. Bickerton
Conservation Division Agent