

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

March 13, 1969

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-155-19118-0000

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 17 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Company

Complete Address: Box 287, Great Bend, Kansas 67530

Lease Name: Dutton Well No. 1

Location: NW NW SE Sec. 21 Twp. 26 Rge. 9 (E) (W) X

County: Reno Total Depth 4405' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Push 5½" plug to 3400'. Fill hole with sand to 3375' and cement with

5 sacks cement. Fill hole with mud to 260'. Set rock bridge from 260'

to 250' and cement hole with 25 sacks cement. Fill hole with mud to 40'.

Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent