

State of Kansas



15-155-19117-0000

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and STATE CORPORATION COMMISSION
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

DEC 18 1968

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 11, 1968

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Messman-Rinehart Oil Company

Complete Address: 1432 Wichita Plaza, Wichita, Kansas 67202

Lease Name: Saylor Well No. 1

Location: E/2 E/2 NW Sec. 21 Twp. 26 Rge. 9 (E)(W)X

County: Reno Total Depth 4176' Oil Well

Gas Well XX Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

(Operator had filled hole with sand to 3795') Dump 5 sacks cement on
sand at 3795'. Fill hole with mud to 280'. Set rock bridge from 280'
to 270' and cement hole with 25 sacks cement. Fill hole with mud to 40'.
Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

St. Aubert J. Lomen
Conservation Division Agent