



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

November 11, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-155-39320-0000

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1970
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. John Glen of Pipe Pullers, Inc. has this
date requested permission to plug the following described well:

Mr. Glen guarantees payment of the plugging fee.

Operator's full Name: George R. Shaw

Complete Address: 826 Union Center, Wichita, Kansas 67202

Lease Name: Edna Brown Well No. 2

Location: C NE NE Sec 22 Twp. 26 Rge. 9 (E) (W) X

County: Reno Total Depth 3270' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Glen was instructed to plug the well as follows:

Push 5 1/2" plug to 2440'. Fill hole with sand to 2400' and cement hole
with 10 sacks cement. Fill hole with mud to 290'. Set rock bridge from
290' to 280' and cement hole with 25 sacks cement. Fill hole with mud
to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks
cement.

Very truly yours,


Conservation Division Agent