

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1966

CONSERVATION DIVISION
Wichita, Kansas

8-10-66

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-155.30145-0000 August 2, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. John Jones of Southwest Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: Sierra Petroleum Company

Complete Address: 211 N. Broadway, Wichita, Kansas

Lease Name: Fluke Well No. 1

Location: C NE ^{SW} SE Sec. 23 Twp. 26 Rge. 9 (E) (W) X

County Reno Total Depth 3265' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Jones was instructed to plug the well as follows:

Push 4 1/2" plug to 2225'. Fill hole with sand to 2215' and cement with
3 sacks. Fill hole with mud to 225'. Set rock bridge from 225' to
215' and cement hole with 20 sacks. Fill hole with mud to 40'.
Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

William J. Loman
Conservation Division Agent