



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JAN 4 1968

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

5-155-26043-0000

December 29, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wayne Dobbs of E. K. Edmiston Drlg. Co., Incas this date requested permission to plug the following described well:

Mr. Dobbs guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First Nat'l Bank Bldg., Wichita, Kansas 67202

Lease Name: Crotts "B" Well No. 1

Location: C SE SE Sec. 30 Twp. 26 Rge. 9 (E) (W) X


County: Reno Total Depth 3985' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dobbs was instructed to plug the well as follows:

Fill hole with mud to 230'. Push plug and 1/4 sack hulls to 230' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent