

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-155 02383-0000 March 28, 1966

RECEIVED  
STATE CORPORATION COMMISSION

APR 5 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Sam Bradley of Pipe Pullers, Inc. has this

date requested permission to plug the following described well:

Mr. Bradley guarantees payment of the plugging fee.

Operator's full Name: Edwin G. Bradley

Complete Address: 826 Union Center, Wichita, Kansas

Lease Name: Foster "A" Well No. 1

Location: C SE NW Sec. 32 Twp. 26 Rge. 9 (E) (W) X

County Reno Total Depth 3998' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Bradley was instructed to plug the well as follows:


Fill hole with sand to 3930' and cement with 5 sacks.

Fill hole with mud to 310'. Set rock bridge from 310' to 300' and

cement hole with 25 sacks. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
Conservation Division Agent