

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

~~We also are in need of a well log on this well~~ Form CP-4

WELL PLUGGING RECORD

Sedgwick

County. Sec. 26 Twp. 25 Rge. 1W 1E11 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner Time Petroleum Company

Lease Name Underwood

Well No. 1

Office Address 815 Union National Bldg., Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed 7/9/61 19

Application for plugging filed 7/9/61 19

Application for plugging approved 7/9/61 19


Plugging commenced 7/9/61 19

Plugging completed 7/9/61 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Lee Guthrie

Producing formation Depth to top Bottom Total Depth of Well 2758' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Squeezed 20 sacks cement on Bottom by United Cementing Company
at 240' Set 20' Rock Bridge and 20 sacks cement. Mud to
35' set 5' Rock Bridge 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 28 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Smith-Smith Casing Pulling Co.
Address Box 8 - Cushing, Okla.

STATE OF Kansas COUNTY OF Sedgwick ss.

Employee of owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

815 Union National Bldg.
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of April, 1966

My commission expires 9-6-69

Josephine Danner
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


COPY ^a

Company- **TIME PETROLEUM**
Farm- **Underwood** No. **1**

SEC. **26** T. **25** R. **1W**
SE NE NW

Total Depth. **3742'**
Comm. **5-24-58** Comp. **6-9-58**
Shot or Treated.
Contractor. **Target Drig. & Prod.**
Issued. **8-16-58**

County **Sedgwick**
KANSAS



Elevation. **1359' RB**

Production. **25 BOPD**

CASINO:

8 5/8" **266'** **cem w/275 sx.**
5 1/2" **2765'** **cem w/75 sx.**

Figures Indicate Bottom of Formations.

surface hole	266
shale lime shells	575
shale lime strks	925
shale	1580
shale - lime shell	1790
lime - shale	1920
lime	2015
shale - lime	2145
shale - lime streak	2265
shale	2365
shale - lime	2415
lime	2685
lime	2764
lime	2840
lime-shale	2980
lime	3130
shale- lime - chert	3198
lime	3334
lime - chert	3413
lime	3480
lime - shale	3602
shale - lime - chert	3675
sand	3686
shale - sand	3709
sand	3732
Arbuckle	3742
Total Depth	

TOPS: SCOUT

Kansas City	2620
Mississippi	3190
Viola	3625
Simpson	3660
Arbuckle	3730

DST #1 shut in 30 min., tool op 1 hr.,
shut in 30 min, IBH 1010#, FBHP 865#,
HH 145# Flow 20"

DST #2 2703-2717', rec. 60' oil cut
mud BHP 985#.

DST #3 - -

RECEIVED
STATE CORPORATION COMMISSION

APR 29 1966

CONSERVATION DIVISION
Wichita, Kansas