


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

KIOWA County, Sec. 26 Twp. 27 Rge. (E) 19 (W)
Location as "NE/CNW/SE/SW" or footage from lines C SE SW
Lease Owner MARTIN OIL COMPANY
Lease Name PYLE Well No. B #1
Office Address 527 Union Center Building, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 12/19 19 73
Application for plugging filed 12/19 19 73
Application for plugging approved 12/19 19 73
Plugging commenced 12/19 19 73
Plugging completed 12/19 19 73
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well RUSSELL BIBERSTEIN
Producing formation Depth to top Bottom Total Depth of Well 4841 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand, shale and shells		0	514	8 5/8	514	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

23 saks at 500'
25 saks at 250'
10 saks @ 40'
2 saks in rat hole


RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Gabbert-JONES (employee of owner) or (owner/producer) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack W. Gabbert
830 Sutton Place, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 25 day of January, 19 74



Nov. 29, 1975
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

PYLE B #1
C SE SW, Sec. 26-27S-19W
Kiowa County, Kansas

COMMENCED: December 6, 1973
COMPLETED: December 19, 1973

OPERATOR: MARTIN OIL COMPANY

Depth		Formation	Remarks
From	To		
0	169	Sand-Shale	Ran 13 double jts. of used 8 5/8" casing set @514' w/450 sacks common cement, 20 Gal-38 CC. P.D. @6:15 AM. 12-7-73. Cement circulating.
169	518	Shale-Shells	
518	870	Redbed-Shale	
870	1205	Shale-Shells	
1205	1235	Anhydrite	
1235	1720	Shale-Shells-Salt	
1720	2290	Shale-Shells	
2290	2415	Lime-Shale	
2415	2875	Lime	
2875	3255	Lime-Shale	
3255	3380	Shale-Lime	
3380	3815	Lime-Shale	
3815	4826	Lime	
4826	4841	Chat	

Dry and Abandoned.

RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1974
CONSERVATION DIVISION
Wichita, Kansas

4841 T.D.

I, Jack W. Gabbert, certify this is a correct copy of the Drillers' Log for the well drilled in the C SE SW of Sec. 26-27S-19W, Kiowa County, Kansas to the best of my knowledge and belief.

Jack W. Gabbert

JACK W. GABBERT

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 21st day of December, 1973, personally appeared Jack W. Gabbert to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.



Marjorie Hall

MARJORIE HALL-NOTARY PUBLIC