


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 16 Twp. 27S Rge. 20W (X) (W)
Location as "NE/CNW/SW" or footage from lines C SE NW
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name Brensing Well No. A-#1
Office Address 909 Palace Bldg., Tulsa, Okla. 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-16-67 19
Application for plugging filed 6-16-67 19
Application for plugging approved 6-16-67 19
Plugging commenced 6-16-67 19
Plugging completed 6-16-67 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4969 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	403'	same
				8 5/8"	452.74'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pushed plug to 350', set bridge, 1/2 sk. hulls & 25 sks. cement
Filled with mud to 40', set plug, 1/2 sk. hulls & 10 sks. cement
put 2 sks. cement in rathole

RECEIVED
STATE CORPORATION COMMISSION

JUN 21 1967
6-21-67

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of June, 1967

My commission expires April 1, 1971 Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Herman Geo. Kaiser, Oil Producer
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: BRENSING A-#1
 LOCATION: C SE NW SEC. 16-27S-20W
 KIOWA COUNTY, KANSAS
 COMMENCED: 5-29-67
 COMPLETED: 6-16-67

0	120	Sand, Clay, Gravel
120	695	Shale
695	1325	Redbed
1325	1357	Anhydrite
1357	1450	Shale, Shells
1450	1784	Shale
1784	2447	Shale, Lime
2447	3165	Lime, Shale
3165	3300	Chalky Lime, Shale
3300	3485	Lime, Shale
3485	3760	Lime
3760	3950	Lime, Shale
3950	4373	Lime
4373	4524	Lime, Shale
4524	4676	Lime
4676	4730	Lime, Shale
4730	4969	Lime
	<u>4969</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 21 1967
 CONSERVATION DIVISION
 Topeka, Kansas

Ran 9 joints of 8 5/8" new 20# surface casing, set @ 403' cemented with 300 sacks Common cement with 2% cc and plug down @ 1:30 a.m. 5-30-67 cement circulated. Surface pipe split @ 20' and @ 140'; reamed pipe and recovered then ran 10 joints of new 8 5/8" 20# surface casing with guide shoe, set @ 452.74', cemented with 400 sacks Common cement with 2% cc, plug down @ 9:45 a.m. 6-8-67

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Brensing A-#1 Well, located C SE NW of Section 16, Township 27 South, Range 20 West, Kiowa County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 20th day of June, 1967.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971