

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County. Sec. 8 Twp. 27 Rge. 20W E7W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

1980' ESL & 1320' FEL
Lease Owner Wells Energy Corp.
Lease Name Einsel Well No. 1

Office Address Suite 454 700 S. Colorado Blvd, Denver,
Character of Well (Completed as Oil, Gas or Dry Hole) CO
Dry Hole 8022:



Locate well correctly on above
Section Plot

Date Well completed July 14, 1980
Application for plugging filed Verbal Application 1980
Application for plugging approved Verbal Approval 1980
Plugging commenced July 14, 1980
Plugging completed July 14, 1980
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 1980

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,944'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	531'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,944 ft. (rotary total depth) to 510 ft. Set plug at 510 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 510 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole, 5 sacks cement in mouse hole, and 5 sacks cement in water well.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~(employee of owner)~~ ~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water #10, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 1980

Elsie Willison
Elsie Willison - Notary Public.

My commission expires July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1980

CONSERVATION DIVISION
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Wells Energy Corp.

SEC. 8 T. 27 R. 20W
LOC. 1980' FSL & 1320' FEL

FARM Einsel NO. 1

COUNTY Kiowa

ROTARY TOTAL DEPTH 4,944'

COMM. July 2, 1980

COMP. July 14, 1980

CONTRACTOR H-30, INC. (Rig #77)

ISSUED August 7, 1980

CASING

10 3/4"

8 5/8" Set at 531' cemented w/450 sxs cement

ELEVATION 2,312' K.B

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	72'
Sand and Red Bed	533'
Red Bed and Sand	2,198'
Lime and Shale	2,402'
Shale and Lime	2,557'
Lime and Shale	4,944'
Rotary Total Depth	4,944'


I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas)
) ss:
County of Kansas)

Subscribed and Sworn to before me a Notary Public in and for said county and state this 7th day of August, 1980.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

AUG 27 1980

CONSERVATION DIVISION
Wichita, Kansas