

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-097-20-982 20976-0000

LEASE NAME Einsel "K" #1

WELL NUMBER _____

SPOT LOCATION 1980' ESL & 660'

SEC. 7 TWP. 27s RGE. 20w (E) or W

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced 6/11/84

Plugging Completed 6/15/84

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR TXO Production Corp.

ADDRESS 200 W. Douglas, Suite 300, Wichita, Ks. 67202

PHONE # (316) 265-9441 OPERATORS LICENSE NO. #5171

Character of Well _____
 (Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4950'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	602'	none
				4 1/2"	4949'	2698'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 4800' & 4 sacks cement. Shot pipe at 4230', 4027', 3837', 3519', 3224', 3014', 2922', & 2699'. Pulled total of 66 joints. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, 8 5/8 plug, & 150 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
 Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED
 STATE CORPORATION COMMISSION

JUN 20 1984

CONSERVATION DIVISION
 Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 19th day of June, 1984

 IRENE HOOVER
 State of Kansas
 My Comm. Exp. Aug. 15, 1985

Irene Hoover
 Notary Public

My Commission expires _____