

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-20,369-0000

LEASE NAME Pyle

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR TGT Petroleum Corp.

SEC. 35 TWP. 27S RGE. 19 (E) or (W)

ADDRESS 7570 W. 21st-Bldg. 1010-D. Wichita, Ks.

COUNTY Kiowa

PHONE# (316) 773-2266 OPERATORS LICENSE NO. 5118

Date Well Completed 1-20-77

Character of Well Depleted

Plugging Commenced 11/27/00

(Oil Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/1/00

The plugging proposal was approved on _____ (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation Mississippi Depth to Top _____ Bottom _____ T.D. 4840

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	322	-0-
				5 1/2	4899	2997.1

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Fill with sand to 4640'; dump five sacks cement. Pull to 1200'. Pump five sacks gel and 50 sacks cement. Pull to 40' and circulate. All cement 60/40 Posmix/w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

RECEIVED
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss. **JAN 08 2001**


B. Lynn Herrington (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington

(Address) 7570 W. 21st-Bldg. 1010-D
Wichita, Ks. 67205

SUBSCRIBED AND SWORN TO before me this 3rd day of January, 2001

Judith K. Moser Notary Public



My Commission Expires: May 17, 2001

DRILLERS LOG

PYLE #1

CASING RECORD:
8 5/8" set at 321.90
with 250 sacks cement

OPERATOR: Barnett Oil, Inc.

DESCRIPTION

CONTRACTOR: Search Drilling Company

SE SE,
Section 35-27S-19W
Kiowa County,
Kansas

TOTAL DEPTH:

COMMENCED: December 28, 1976

4900'

COMPLETED: January 6, 1977

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay-Roots and Sand	0	57	
Water-Gravel and Sand	57	180	
Shale	180	335	
Red Bed and Shale	335	1200	
Anhydrite and Shale	1200	1273	
Shale and Lime	1273	1644	
Lime and Shale	1644	1994	
Shale and Lime	1994	2434	
Shale and Lime	2434	3108	
Shale and Lime	3108	3945	
Shale and Lime	3945	4250	
Shale and Lime	4250	4640	
Lime and Shale	4640	4820	
Mississippi	4820	4900	Set 122 joints of new 5 1/2" - tally at 4902, set 1' off bottom with 100 sacks 50-50 posmix - 18% salt - 3/4 of 1% CFR-2, plug down at 10:50 P.M.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RECEIVED
KANSAS CORPORATION COMMISSION

R. M. Stagl
Search Drilling Company
R. M. Stagl

JAN 08 2001

CONSERVATION DIVISION
WICHITA, KS

Subscribed and sworn to before me this 7th day of January, 1976.

My Commission expires:
February 19, 1977

Maxine Dressen
Maxine Dressen Notary Public

MAXINE DRESSEN
NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. FEB. 19, 1977