


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Kiowa County. Sec. 35 Twp. 27 Rge. 19W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NW NE

Lease Owner TGT Petroleum Corporation
Lease Name ASHLEY Well No. 1
Office Address 209 E. William, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed Oct. 18 19 79
Application for plugging filed (verbally) Oct. 18 19 79
Application for plugging approved (verbally) Oct. 18 19 79
Plugging commenced Oct. 18 19 79
Plugging completed Oct. 18 19 79
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Rankins
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4845'
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 4845'
Set 1st plug at 600' with 50 sacks
2nd plug at 300' with 25 sacks
3rd plug at 40' solid bridge with 12 sacks
5 sacks in the rathole.
Cemented with 50/50 posmix, 4% gel.
Plug was down at 7:00 p.m., 10-18-79.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc

STATE OF Kansas COUNTY OF Sedgwick ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 19 79,



Sherrie L. Brooks
Sherrie L. Brooks Notary Public.

My commission expires 08-21-82

CONTRACTOR'S WELL LOG

OPERATOR: TGT Petroleum Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Ashley #1
 LOCATION: C NW NE, Section 35-27-19W,
 Kiowa County, Kansas
 SPUD DATE: October 04, 1979
 COMPLETION DATE: October 18, 1979

0	362	Sand
362	399	Red beds and shale
399	935	Shale and red beds
935	1210	Red beds and shale
1210	1226	Anhydrite
1226	1706	Red beds and shale
1706	2123	Shale and lime
2123	4845	Lime and shale
	4845	Rotary Total Depth

Spud hole at 5:30 p.m., October 04, 1979. Drilled 362' of 12 1/4" hole. Ran 12 joints of used 8-5/8" - 24# casing. Set at 362' with 350 sacks of Class A cement, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 11:30 p.m., October 04, 1979.

T.D. 4845'. Set 1st plug at 600' with 50 sacks, 2nd plug at 300' with 25 sacks, 3rd plug at 40' solid bridge with 12 sacks, 5 sacks in the rathole. Cemented with 50/50 posmix, 4% gel. Plug was down at 7:00 p.m., October 18, 1979.

SAMPLE TOPS:

Anhydrite 1210'
 B/Anhydrite 1226'

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 25 1979
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Ashley #1, C NW NE, Section 35-27-19W, Kiowa County Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 23rd day of October, 1979.

 **SHERRIE L. BROOKS**
 Sedgwick County, Ks.
 My Appt. Exp. 8-21-82

Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 08-21-82.