


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County. Sec. 10 Twp. 27 S Rge. 20 (E) W (W)
Location as "NE/CNW/SSW" or footage from lines C SW NW
Lease Owner Mull Drilling Company
Lease Name Morford Well No. 1
Office Address 1625 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 9/23 19 67
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/23 19 67
Plugging completed 9/23 19 67
Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 5183 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface hole	water	surface	490'	8 5/8"		left in
(see attached log)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom plug at 400 feet, 1/2 sacks hulls, 25 sacks cement.

top plug at 40 feet, 1/2 sacks hulls, 16 sacks cement.

25 sacks in rathole.

RECEIVED
SEP 23 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Donelson Drilling Company
Address 619 First National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
James L. Donelson

(Signature of owner or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

James L. Donelson

619 First National Bank Building
(Address)

Subscribed and Sworn to before me this 27th day of September, 19 67

Carolyn L. Scott
Notary Public.

My commission expires April 16, 1967

MORFORD #1

Mull Drilling Company

Total Depth: 5183'

Elevation: 2364' GL, 2369' KB

Contractor: Donelson Drilling Co.

Location: C SW NW, 10-²⁹~~25~~-20W

Commenced: 9/8/67

Kiowa County, Kansas

Completed: 9/23/67

Casing Record: 490' new 8 5/8"
w/250' sx cmt. and 5' sx gel w/3% CC

Formation:

Depth:

Surface hole	496'
Shale	524'
Anhydrite	534'
Shale & Shells	659'
Sand & Shale	925'
Shale & Lime stks.	1314'
Anhydrite	1345'
Shale	1470'
Shale & Lime	2618'
Lime	2715'
Lime w/Shale stks.	2832'
Lime	2946'
Lime & Shale brks.	3071'
Lime & Shale	3175'
Lime	3189'
Lime & Shale	3860'
Lime	4005'
Lime & Shale	4202'
Lime	4295'
Lime & Shale	4527'
Lime	5183' TD

RECEIVED
STATE CORPORATION COMMISSION
SEP 28 1967

CONSERVATION DIVISION

I hereby certify the foregoing statements are true and correct
to the best of my knowledge and belief.

DONELSON DRILLING COMPANY

James L. Donelson
James L. Donelson

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public in and for
said county and state, this 27th day of September, 1967.

My Commission expires: April 16, 1969.

Carolyn L. Scott
Carolyn L. Scott